

		OBIEKT		AMFITEATR							26/W	
		ELEMENT		PREFABRYKATY PP5, PP6.1 PP6.2								
ZESTAWIENIE STALI ZBROJENIOWEJ												
Rodzaj elementu	Nr pręta	Średnica pręta	Długość pręta	Ilość			Długość łączna					
				Prętów w elemencie	Elementów w budowlu	Razem prętów	Stal B500B lub B500SP					
							# 8	# 10	# 12	# 16	# 18	
		mm	m/mb	szt.	szt.	szt.	m	m	m	m	m	
PP5	1.1	10	1,12	37	7	259		290,08				
	1.2	16	1,12	16	7	112				125,44		
	1.3	10	1,50	47	7	329		493,50				
	2.1a	10	5,18	3	7	21		108,78				
	2.2a	16	5,18	10	7	70				362,60		
	2.3a	20	5,18	10	7	70						
	3	10	1,01	77	7	539		544,39				
	3.1	10	0,98	7	7	49		48,02				
	4	8	0,85	10	7	70	59,50					
	5	10	1,22	7	7	49		59,78				
6	8	0,81	10	7	70	56,70						
7	8	1,10	44	7	308	338,80						
PP6.1	1.1	10	1,12	38	4	152		170,24				
	1.2	16	1,12	16	4	64				71,68		
	1.3	10	1,50	47	4	188		282,00				
	2.1b	10	5,53	3	4	12		66,36				
	2.2b	16	5,53	10	4	40				221,20		
	2.3b	20	5,53	10	4	40						
	3	10	1,01	70	4	280		282,80				
	3.1	10	0,98	7	4	28		27,44				
	3.2	10	1,12	7	4	28		31,36				
	4	8	0,85	10	4	40	34,00					
7	8	1,10	44	4	176	193,60						
8	8	1,40	10	4	40	56,00						
PP6.2	1.1	10	1,12	38	3	114		127,68				
	1.2	16	1,12	16	3	48				53,76		
	1.3	10	1,50	47	3	141		211,50				
	2.1b	10	5,53	3	3	9		49,77				
	2.2b	16	5,53	10	3	30				165,90		
	2.3b	20	5,53	10	3	30						
	3	10	1,01	70	3	210		212,10				
	3.1	10	0,98	7	3	21		20,58				
	3.2	10	1,12	7	3	21		23,52				
	4	8	0,85	10	3	30	25,50					
7	8	1,10	44	3	132	145,20						
9	8	1,11	10	3	30	33,30						
Razem						[m]	942,600	3049,900		1000,580		
Masa jednostkowa						[kg/m]	0,329	0,617	0,888	1,580	2,000	
Ciężar łączny						[kg]	310,1	1881,8		1580,9		
OGÓŁEM						[kg]	3772,8					

W zestawieniu stali nie ujęto kotew oraz dozbrojenia dla osadzenia kotew montażowych i transportowych.